SECTION 08380

DOUBLE ACTING IMPACT TRAFFIC DOORS

Part 1 GENERAL

Section 1.01 SUMMARY

- A. This section includes double acting impact traffic doors.
- B. Related sections: Include appropriate section below indicating proper frame/jamb details. Recommended jamb is ½" thick and 4" wide minimum steel frame.

Section 1.02 SUBMITTALS

- A. Product data: Submit manufacturer's data indicating products provided.
- B. Shop drawings: Submit indicating locations of required block outs, frame fabrication requirements, sizes, elevations, and other related items.

Section 1.03 DELIVERY, STORAGE AND HANDLING

- A. Packing and shipping: Deliver work packaged for protection.
- B. Acceptance at site:Inspect work upon delivery for damage; rejecting any damaged items.
- C. Storage and protection: Store materials under cover, 4" off floor, minimum, raised platforms, in vertical position with minimum ¼" space between doors. Avoid use of non vented plastic or canvas shelters creating humidity chambers. Immediately remove wet wrappers.

Part 2 PRODUCTS

Section 1.04 MANUFACTURERS

- A. Acceptable Manufacturers:
 - 1. Products specified as standard of quality are manufactured by:

National Access Design, LLC 1924 Losantiville Ave. Cincinnati, OH. 45237 1-513-351-3400

www.nationalaccessdesign.com

2. Substitutions: Not permitted

Section 1.05 MANUFACTURED UNITS

- A. Traffic Doors:
 - 1. Acceptable product: National Access Design Model 9500
 - 2. Traffic type: Retail/Commercial, Light to Medium duty Cart and Personnel.
 - 3. Sizes: As indicated on drawings (door schedule).

DATE: 6-16-2020 DOUBLE ACTING TRAFFIC DOORS

4. Panels:

- a. 1 3/4" thick, rigid welded aluminum framing with .125 ABS facings. Fully insulated with polystyrene insulation. Perimeter of panels to be fully gasketed.
- b. Ridged heavy duty back edge spine.
- c. Color; Architect to chose color from standard manufacturer's

5. Hinges:

a. Hinges are V-Cam with 10" jamb guard standard.

6. Vision Area:

- a. 9" X 14" clear vision panels held securely in place by low profile high strength plastic sealed frames.
- b. Or 6" x 12" (If panels are 42"Bi-parting or smaller) (If not used should be removed at final draft)
- c. Or 14" x 16" (If not used should be removed at final draft)
- d. Or 22" x 22" (If not used should be removed at final draft)
- e. Or 10" X 30" ADA

7. Panel Protection: Teardrop Bumper

- a. None
- b. Or 12" high Teardrop bumper(If not used should be removed at final draft)
- c. Or 18" high Teardrop bumper(If not used should be removed at final draft)
- d. Or 24" high Teardrop bumper(If not used should be removed at final draft)
- e. Or 36" high Teardrop bumper(If not used should be removed at final draft)
- f. Or 42" high Teardrop bumper(If not used should be removed at final draft)

8. Panel Protection: Impact Plate

- a. None
- b. Or 12" high Impact plate(If not used should be removed at final draft)
- c. Or 18" high Impact plate (If not used should be removed at final draft)
- d. Or 24" high Impact plate (If not used should be removed at final draft)
- e. Or 36" high Impact plate (If not used should be removed at final draft)
- f. Or 42" high Impact plate (If not used should be removed at final draft)
- g. Or 48" high Impact plate (If not used should be removed at final draft)

Part 3 EXECUTION

Section 1.06 EXAMINATION

A. Verification of conditions:

- 1. Verify traffic door frames are in accord with reviewed shop drawings.
- 2. Examine conditions and substrates under which products of this section are to be installed; submit written notification of unacceptable conditions or substrates.
- 3. Submit copy of installer's report to Architect of record within 72 hours of report receipt.
- 4. Proceeding with construction activity of this section:
 - a. Prior to correction of unacceptable conditions or substrates are prohibited.

DATE: 6-16-2020

b. Indicated installer's acceptance of condition of product and substrates.

Section 1.07 INSTALLATION

- A. Steel tube frames: Or minimum 2 X 4 double wood, C-Channel or reinforced hollow metal frames. Installed in Metal Fabrication section.
- B. Traffic doors:
 - 1. Install in prepared openings in accordance with reviewed shop drawings and manufacturer's Installation instructions
 - 2. Plumb and level units.
 - 3. Adjust for proper operation.
- C. Clean surfaces per manufacturer's instructions just prior to Date of Substantial Completion.

++ END OF SECTION ++

DATE: 6-16-2020